BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of the Work: Desilting of drains in Devinagar, Lottegollahalli and surrounding area in ward no. 08 Kogiehalli.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	1819.80	Removing & Refixing stone slabs of drains and pointing in CM 1:3) (Page No. 25,Item No. 5.33)	Sqm	80.56	Rupees Two Hundred Eight and Ninety Three Paise Only
2	1815.30	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. (Page No.141, Item No.19.1)	Cum	86.92	Rupees Five Thousand Seven Hundred Twenty Six and Fifty One Paise Only
3	1815.30	Conveying the excavated debries and over burden earth etc., to a lead of 10.00 Km distance by using private vehicle this includes the cost of loading and unloading charges etc., complete	Cum	106.00	Rupees Six Thousand Nine Hundred Seventeen and Twenty Three Paise Only

4/06

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

04/06

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

DTS Approved

Chief Engineer
Yelahanka Zone
Bruhath Bangalore Mahanagara
Palike
Bangalore 92